

Safe Work Method Statement – Structural alterations that require temporary support to prevent collapse

This SWMS needs to be reviewed against site conditions upon commencing work. Where site conditions prevent works to be carried out in accordance with this SWMS than another is to be written and Site Supervisor notified.

Principle Builder:	Blakes Master Builders	Contractor:		
Builder Contact Phone:	53 452 632	Work Location:		
High Risk Construction Work:	Structural alterations that require	Site Supervisor	Paul Talbot, Mick Robinson or Brad Blake	
	temporary support to prevent collapse			
Date of SWMS:		Review Date:		
What measures are in place to ensure	Blakes Master Builders will conduct regular site Audits to ensure compliance of this or any other SWMS.			
compliance with the SWMS?				
Have workers been consulted about the	All workers are required to be consulted with regards to the SWMS and control measures contained in the SWMS.			
SWMS?				
Person Responsible for ensuring	Different contractors will encounter different high-risk activities. All contractors are responsible for reviewing this SWMS against site conditions			
compliance with SWMS	and ensure work occurs in accordance with the SWMS.			
Person Responsible for reviewing the	Contractors should review this SWMS and apply the control measures outlined for the various high-risk activities that they may undertake.			
SWMS	When works cannot occur in accordance with this SWMS then contact is to be made with the site supervisor.			

Tasks Involved	What are the hazards and risks?	What are the control measures for the hazards?	
Pre-start check at site	-Site hazards may impair works	• Undertake pre-site inspection verify conditions on site will enable works to be carried out in accordance with the	
		SWMS.	
		• Discuss site specific works with the Site Supervisor reviewing site signage, Safety Management Plan, for site	
		specific hazards	
		Ensure all employees are made aware of any site specific hazards to works and this SWMS	
		If SWMS are to be changed copy is to be provided to site supervisor and approval obtained	
		Construction Inducted employees and contractors are only allowed to undertake construction works	
		Inspect meter box RCD and activate tripping device verifying working condition if using power equipment	
		Ensure all leads tagging & testing are up to date.	
		Only certified and/or licensed personnel are to operate mobile equipment	
Isolate unsupported	-Falling object	Where it is assessed that a structure is likely to collapse it is to be isolated from workers and members of the	
structure		public via the installation of temporary fencing, bollards, warning tape, and signage. A combination of these control	
		measures can be employed to prevent access	
		The exclusion zone should encompass the area in-which the structure is likely to collapse	
		Workers are not to walk under unsupported structure or in the exclusion zone	

		 Where structural support is required an engineers assessment is required as to the type, number, method of
support		installation, and location of structural supports
		Where an engineer's report is not available contact Site Supervisor
	-Falling materials	• The engineers report forms part of the requirement to be followed while undertaking the installation of structural
support		support.
		• Instruction for type and number of supports are to be followed.
		• Installation is to occur in a methodical manner following engineer's recommendation. The first support installed at the nearest entry point and subsequent supports to be installed sequentially
		• Workers are not to walk under unsupported structure or in the exclusion zone until the structure has been
		supported. Safety hats are to be worn.
		Supports are to be to secured into place to prevent movement
Removing structural parts	-Collapse of structure	• Prior to any removal/demolition work being undertaken and at the start of each shift, all temporary supports will be checked to ensure that they are still working correctly.
		• If their sign supports are failing or not secure the area is to be cleared and the site supervisor contacted to have the supports corrected.
		A removal plan prepared by an engineer must be followed for correct sequence of removal
		Where there is no removal plan contact site supervisor
Removing temporary supports	-Collapse of structure	 Temp support must not be removed until structure is stable and in the condition as set out in the engineers report. Structure is to be inspected by a suitably qualified building representative prior to removal of propping. If inspection has not occurred or can not be verified contact Site Supervisor prior to removing props Supports will be removed in the order as outlined in the engineers report or if not defined in a sequential manner.
Install temporary	-Falling object	Ensure adequate bracing to structures. Define & barricade working areas.
support during brick wall		 Supports will need to be spaced at intervals of no more than 3m between bracing
construction- free		Height of unsupported brick work above the bracing is to be no more than 900mm
standing wall		Supports are to be fitted to both sides of the unsupported wall
Temporary support for wall frames	-Collapse of structure	In general temporary supports for wall frame are installed to assist with keeping the frames in line during construction. Where frames are not fully completed they may become unstable due to bad weather, wind, subsidence, construction loads, live loads, and the premature removal of temporary bracing or propping. Ensure that any uncompleted frames are temporarily supported via bracing. Temporary bracing should be ready before standing of wall trusses commences (as a guide a minimum of two braces per frame is required): • Stand frame part way to vertical position and hold until a temporary brace is attached
		The brace should then be nailed off and other braces attached as necessary
Temporary supports	-Collapse of structure	Prior to loading the top plates with roof trusses the frame installer is to ensure:
required for wall frame		• All wall frames are secured and nailed off and adequately braced with permanent and temporary bracing to take
pre loading of trusses		all loads imposed during truss erecting, including the placement of trusses on the roof

Name of Worker	Date	Signature